

MCA

Machine Room Elevator Planning Guide


The information in this catalogue is subject to change without notice. The information and diagram in this catalogue reflect the technical feature and configuration of the elevator model at press time (refer to the version number). In line with the principle of continuous development of products, our company reserves the right to change the selection of product technical parameters and colour at any time. The existing image technology cannot accurately reproduce the elevator component structure and decoration colour. Therefore, this catalogue only provides general information, not as a contract document. The specific configuration parameters are subject to the formal agreement.

If you need detailed information, please contact us.

02 Specification
 03 Layout
 04 FI System
 07 Elevator Function
 09 Overhead Height and Pit Depth
 11 Hoistway and Machine Room
 27 Entrance Design
 29 Electrical Data
 31 Electrical Information
 32 Civil Works Matters


Load (kg)	No. of Passengers ^①	Speed (m/min)	Maximum Number of Stops	Maximum Travel (m)	Maximum Travel with Fireman Operation (m)	Minimum Floor Height (mm)
450	6	60/90/105	60m/min:22 90m/min:24 105m/min:24	60	—	2800
630	8	60/90/105	60m/min:22 90m/min:40 105m/min:40 120m/min:48 150m/min:48 180m/min:48	60m/min:60 90m/min:100 105m/min:100 120m/min:140 150m/min:140 180m/min:150	—	
825	11	60/90/105/120/150/180			60m/min:58 90m/min:86 105m/min:99,5 120m/min:115 150m/min:140 180m/min:150	
900	12	60/90/105/120/150/180				
1050	14	60/90/105/120/150/180				
1150	15	60/90/105/120/150/180				
1350	18	60/90/105/120/150/180				
1600	21	60/90/105/120/150/180				
1800	24	60/90/105/120/150				
2000	26	60/90/105/120/150				

Note:
 ① Passenger numbers calculated at 75kg per person.
 ② The information above are based on GB standards.




- Maximum in-line arrangement is 4 elevators.
- Elevators in different groups should not be set in the same line.
- Avoid placing the elevators entrance near pillars.

- More than 5 units in the same group, the elevators should be set face-to-face. And the distance of facing elevators (L) should be 3.5~4.5m.
- Different group elevators with face-to-face arrangement, the distance of facing elevators (L) should be more than 6m.



- Elevators in same group should have same stops.
- Elevators in same group should be set the same floor as basement and not recommend to set several entrance.



<FI-600 Features> Future Reference-Trajectory Control

A group control system groups multiple elevators for achieving a well-balanced operation by taking waiting times into account. Such a system requires flexibility so that it can be used in various types and sizes of buildings and be responsive to changing traffic demand.

(FI-600)	(FI-100)	(FI-10)
(3-8 Cars)	(3-6 Cars)	(3-4 Cars)
Allows a flexible control for elevator car allocation and the required number of cars according to the congestion state in the building and the type of building.	Elevator cars are allocated at equal time intervals according to "Reference-Trajectory Control" for shortening the average waiting times and reducing the probability of a long wait.	Provides a ring control to allocate the elevator car closest to the floor where a new hall call is registered.

Basic Specification	Instantaneous reservation and service forecasting		
	Intelligent function		
	Generation of new traffic flow modes Generation of optimum operation programs		
	Congested floor recognition		
	Learning function		
	• Collection of usage data • Recognition of traffic flow mode (40/2 modes) • Search for optimum operation program		
	Arrival notice indication (hall lantern and chimes)		
Bunching prevention ①			
	Future reference-trajectory control	Reference-trajectory control	Ring control
	Forecasting dynamic allocation control	Zone distribution control	Fixed floor distribution control
System name	FI-600	FI-100	FI-10
Recommended number of cars in a group	3~8 cars	3~6 cars	3~4 cars
Type of building	Large office buildings and hotels	Small office building, department stores, hotels and hospitals	Building with small traffic demand
Optional	VIP service, independent automatic operation		
	Service floor selection		
	Destination floor reservation system Centralized control for special floors Zoning express service		

Note:

① Bunching prevention: Using the "future reference-trajectory control" or the "reference-trajectory control" in the FI-600 or FI-100, elevator cars are operated at equal time intervals to prevent local bunching.

Basic Function

● : Basic spec. ▲ : Option spec. — : Not applicable

No.	Item	Content	FI-600	FI-100	FI-10
1	Instantaneous reservation and service forecasting (FI-HRF)	Upon receipt of a hall call, this function activates and elevator to serve this call, and at the same time the call is acknowledged by the hall lantern and chime.	●	—	—
2	Arrival notice indication (FI-ANI)	Four to five seconds prior to the arrival of an elevator, this function will activate the hall lantern flickering and the chime sound.	●	●	▲
3	Basic call assignment control	Future reference-trajectory control (FI-FRTC)	●	—	—
		Reference-trajectory control (FI-RTC)	—	●	—
4	Personalized control	Through the hall call assignment control of waiting time priority assignment, constantly carry out operation management in accordance with waiting time priority.	●	●	—
	Waiting time priority assignment	Prevent long waiting time of passengers by implementation of hall call assignment.	●	●	—
	Riding time priority assignment	Prevent long riding time of passengers by implementation of hall call assignment.	▲	▲	—
	Bunching prevention (FI-BP)	This function prevents local bunching of elevator cars using the "future reference-trajectory control" or the "reference-trajectory control" for operating cars at equal time intervals.	●	●	—
5	Learning function	Collection of usage data (FI-CUD)	●	●	—
		Recognition of traffic flow mode (FI-RTM)	● (40 modes)	● (2 modes)	—
		Search for optimum operation program (FI-SOP)	●	●	—
6	Congested floor recognition (FI-CFR)	Identifies congested floors according to the usage data learned in each traffic flow mode.	●	—	—
7	Service forecasting for hall call assignment (FI-SFH)	This function assigns elevator cars to hall calls more precisely by forecasting the arrival time and number of passengers in the car according to the learning-based traffic demand.	●	—	—
8	Intelligent function	Generation of new traffic flow modes (FI-GNT)	●	—	—
		Generation of optimum operation programs (FI-GOP)	●	—	—
9	Energy saving preference control (FI-ESC)	This system reduces the number of elevator cars in service when traffic demand is low.	●	—	—
10	Floor standby control	Forecasting dynamic allocation control (FI-FDA)	●	—	—
		Zone distribution control (FI-ZD)	—	●	—
		Fixed floor distribution (FI-FD)	—	—	●

Basic Function

● : Basic spec. ▲ : Option spec. — : Not applicable

No.	Item	Content	FI-600	FI-100	FI-10
11	Learning based concentrated service (FL-LCS)	Centralizes the service to the learning-based congested floors during peak times including morning, lunch time and evening peaks while taking the service for other floors into account.	●	—	—
12	Rush-hour schedule operation	All the elevators will automatically return to the start floor after serving the last call during this preset rush-hour timing.	●	—	▲
13	Destination floor priority control	The allocation will be priority when the destination floor and the hall call is the same floor.	●	●	—
14	Full car forecasting control	Control the new allocation according to the number of passengers in car and the times of new calls.	●	●	—
15	Full car control	Stop new allocation or re-allocate the car when full load.	●	●	—
16	Long waiting time allocation control	Re-allocate the cars when long waiting time situation is forecasted.	●	●	—
17	Notice function	Keep the service elevator car door open with hall lantern flickering to guide the passengers.	▲	●	—
18	Automatic door open time control (FI-ADT)	This function automatically controls the duration of the door open time according to the floor and the kind of call (hall call or car call) as well as the elevator condition.	●	●	—

Operating Function

No.	Item	Content	FI-600	FI-100	FI-10
1	Centralized control for special floors (FI-CCF)	This function preferentially assigns an elevator to the special floor. (e.g. the director's room)	▲	—	—
2	Service floor selection (FI-SFS) [Floor lock-out operation]	Allows the operator to select the service and non-service floors using, for example, the switches on the control panel.	▲	▲	—
3	VIP service (FI-VIP)	When welcoming or sending off important guest, this function permits an elevator to be summoned directly to the desired car call floor by pushing a specially provided switch.	▲	▲	▲
4	DFRS	Each passenger registers their destination floor on the registration device located at the landing hall and know in advance the designated elevator to take. System assigned one elevator for the passengers with the same destination floor. This helps to reduce congestion in the elevator lobby and improve efficiency.	▲	—	—
5	Zoning express service (FI-EZS)	Start a divided express service when the peak traffic demand takes place in the present time zones.	▲	—	—

Man-machine Function

No.	Item	Content	FI-600	FI-100	FI-10
1	Malicious operation cancelled function	Cancel the allocation when system identifies the call is malicious.	●	●	—
2	Hall information (FI-HI)	General and elevator operation information is indicated on the LED or LCD hall indicator.	—	—	●

Elevator Function

Standard Function

Control System			
SA1	Simplex Collective Control	SA2	Floor Height Self Measurement
SA3	On-Cage (Car Top) Maintenance Operation	SA4	In-Cage Slow Speed Operation
SA5	Machine Room Debugging Operation		
System Protection			
SB1	Over Speed Electrical Protection	SB2	Overspeed Mechanical Protection
SB3	Rope Slipping Running Protection	SB4	Motor Overload (Thermal) Protection
SB5	Automatic Fault Detection	SB6	Automatic Fault Recording
SB7	Standby Regular Auto-Check	SB8	Double Brake-Safety Check Operation
SB9	Synchronous Motor Magnetic Pole Static Test	SB10	Lift-Position Abnormally Auto-Correction Function
SB11	Nearest Landing Operation	SB12	Anti-electromagnetic Interference
Safe Communication			
SC1	Interphone System (5 ways)		
Safe Riding			
SD1	Out of Door-Open Zone Alarm	SD2	Alarm System
SD3	Door Safety Return System	SD4	Full Load Bypass Operation
SD5	Overload Detection System	SD6	Overload Alarm
SD7	Next Drive (Door Open Abnormity)	SD8	Door Opening/Closing Time Abnormity Protection
SD9	Automatic Door Dwell Time Control	SD10	Automatic Door Dwell Time Adjustment
SD11	Number of Runs Indicator	SD12	Multi-Beam Protection ① (Applicable for center opening door without glass panel)
SD13	Inspection Indication in Hall Indicator	SD14	Current Floor Push-button Reopening Function
SD15	Overload Indicator (In Car)		
Emergency Solution			
SE1	Car Emergency Lighting	SE2	Fire Emergency Operation (Automatic)
Design for Comfort			
SF1	Parking Operation	SF2	Automatic Return Function
SF3	Start Torque Auto-Adjustment	SF4	Door-Stop Function (Maintenance)
SF5	Micro Levelling (Travel \geq 45m)	SF6	Advance Door Opening (Speed \geq 120m/min)
SF7	Mischievous Call Cancellation	SF8	Opposite Direction Car Call Cancellation
SF9	Car Light Auto Turn-off	SF10	Car Fan Auto Turn-off
SF11	Abnormal Duration Hall Call Detection (Applicable for Simplex, Duplex and FI-10 only)	SF12	Car Floor Button Flashing ①
SF13	Car Call Deselect Function	SF14	Step-less Speed Control
SF15	Regenerative System Function (For load \geq 1150kg with speed 180/min)	SF16	Door Bypass Detection
SF17	Overloading Hall Call Recovery Function (Applicable for Simplex, Duplex and FI-10 only)		

Note:
① Details, please contact us.

Elevator Function

Optional Function

Control System			
OA1	Simplex Down Collective Control	OA2	Duplex Collective Control
OA3	Duplex Down Collective Control	OA4	FI-10 ①
OA5	FI-100 ①	OA6	FI-600 ①
OA7	Independent Automatic Operation ①	OA8	VIP Service
OA9	Rush Hour Schedule Operation ① (Not applicable for FI-100)		
Safe Communication			
OB1	Contact at Control Panel (RS485)	OB2	Elevator Monitoring System (Computer Type)
OB3	Supervisory Panel (Dry Contact Type)	OB4	Twisted Pair Cable (1 pair) for CCTV
OB5	Twisted Pair Cable (1 pair) for BGM Interface	OB6	Contact at Control Panel (Dry Contact)
OB7	Camera Device Inside the Car		
Safe Riding			
OC1	Multi-Beam + Safety Edge Protection	OC2	Card Reader Interface (In Car) (RS485) ① (Not applicable when OE5 is selected.)
Emergency Solution			
OD1	Fireman Operation (Load \geq 825kg)	OD2	Automatic Rescue Device (ARD) (Maximum travel distance \leq 30m)
OD3	EM. Operation for Power Failure (Manual)	OD4	EM. Operation for Power Failure (Auto)
OD5	Earthquake Emergency Operation	OD6	Pit Flood Operation
Design for Comfort			
OE1	Attendant Operation	OE2	Independent Operation
OE3	Voice Synthesizer	OE4	Arrival Chime (Car Top and Bottom)
OE5	Floor Lock Out Operation ① (Not applicable when OC2 is selected)	OE6	Door Opening Prolong Button
OE7	Hall Call Registration in Car Operating Panel (Applicable when OE1 is selected)	OE8	Sub Car Operating Panel
OE9	Double Opening Function (Not applicable for FI-100 and FI-600)	OE10	Horizontal Car Operating Panel
OE11	Braille Button	OE12	Regenerative System Function ①
OE13	EMC ① (Only applicable together with OE12)	OE14	Micro Levelling (Travel $<$ 45m)
OE15	Operation Status Indication at Hall Indicator	OE16	DFRS (Under FI-600)
OE17	Hall Call Deselect Function (Applicable for Simplex, Duplex and FI-10 only)	OE18	Advance Door Opening

Note:
① Details, please contact us.

Overhead Height and Pit Depth

Load (kg)	Speed (m/min)	Overhead Height OH (mm)		Pit Depth P (mm)	
		Counterweight Location:Rear	Counterweight Location:Side	Counterweight Location:Rear	Counterweight Location:Side
450	60	4550		1450	
	90	4700			
	105	4750		1500	
630	60	4350		1450	
	90	4450			
	105	4550		1500	
825	60	4350		1450	
	90	4450			
	105	4550		1500	
	120	4700		1600	
900	150	5100		1900	
	60	4350		1450	
	90	4450			
	105	4550		1500	
1050	120	4700		1600	
	150	5100		1900	
	60	4350		1450	
	90	4450			

- Note:
- 1) The above information and dimensions are based on GB standards.
 - 2) The overhead height, OH is based on bare ceiling height of 2450mm.
 - 3) The pit depth, P is based on standard vinyl tile finish without floor recess.
 - 4) Configuration is without counterweight safety gear.
 - 5) Configuration is based on decoration weight provision of up to 100kg.

Load (kg)	Speed (m/min)	Overhead Height OH (mm)				Pit Depth P (mm)			
		Counterweight Location:Rear		Counterweight Location:Side		Counterweight Location:Rear		Counterweight Location:Side	
		Travel ≤ 70m	Travel > 70m	Travel ≤ 70m	Travel > 70m	Travel ≤ 70m	Travel > 70m	Travel ≤ 70m	Travel > 70m
1150	60	4700	—	4700	—	1450	—	1450	—
	90	4650	4650	4650	4650	1550	1600	1550	1600
	105	4800	4800	4800	4800	1550	1600	1550	1600
	120	4850	4850	4850	4850	1600	1650	1600	1650
	150	5100	5100	5100	5100	1900	1900	1900	1900
1350	60	4700	—	4700	—	1450	—	1450	—
	90	4650	4650	4650	4700	1550	1600	1550	1600
	105	4800	4800	4800	4850	1550	1600	1550	1600
	120	4850	4850	4900	4900	1600	1650	1650	1650
	150	5100	5100	5100	5100	1900	1900	1900	1900
1600	60	4700	—	4700	—	1450	—	1450	—
	90	4650	4650	4650	4700	1550	1600	1550	1600
	105	4800	4800	4800	4850	1550	1600	1550	1600
	120	4850	4850	4900	4900	1600	1650	1650	1650
	150	5100	5100	5100	5100	1900	1900	1900	1900

- Note:
- 1) The above information and dimensions are based on GB standards.
 - 2) The overhead height, OH is based on bare ceiling height of 2450mm.
 - 3) The pit depth, P is based on standard vinyl tile finish without floor recess.
 - 4) Configuration is without counterweight safety gear.
 - 5) Configuration is based on decoration weight provision of up to 500kg (For load 1150kg / 1350kg) and 350kg (For load 1600kg).

Overhead Height and Pit Depth




Load (kg)	Speed (m/min)	Overhead Height OH (mm)		Pit Depth P (mm)
		Counterweight Location:Rear	Counterweight Location:Side	
1800	60	4550	4600	1500
	90	4550	5050	1500
	105	4700	5250	1600
	120	4800	5300	1650
2000	150	4900	5400	1950
	60	4550	4600	1500
	90	4550	5050	1500
	105	4700	5250	1600
	120	4800	5300	1650
	150	4900	5400	1950

- Note:
- 1) The above information and dimensions are based on GB standards.
 - 2) The overhead height, OH is based on bare ceiling height of 2450mm.
 - 3) The pit depth, P is based on standard vinyl tile finish without floor recess.
 - 4) Configuration is without counterweight safety gear.
 - 5) Configuration is based on decoration weight provision of up to 500kg.

Load (kg)	Speed (m/min)	Overhead Height OH (mm)	Pit Depth P (mm)
825	180	5450	2400
900			
1050			
1150			
1350			
1600			

- Note:
- 1) The above information and dimensions are based on GB standards.
 - 2) The overhead height, OH is based on bare ceiling height of 2450mm.
 - 3) The pit depth, P is based on standard vinyl tile finish without floor recess.
 - 4) Configuration is without counterweight safety gear.
 - 5) Configuration is based on decoration weight provision of up to 500kg (For load ≤ 1150kg) and 250kg (For load 1350kg / 1600kg).

Hoistway and Machine Room



- Note:
- ① Items with "*" shall be furnished by building contractors.
 - ② Hoistway shall not be located next to bedrooms, classroom, ward, library or any other places where low noise is required.
 - ③ The hoistway construction shall be reinforced concrete ring beam with strength C25 or whole hoistway of reinforced concrete wall. If you have other situations, please contact us.
 - ④ For hoistway and machine room details, please contact us.
 - ⑤ Unit of dimension shall be in mm unless otherwise stated.




Load (kg)	Speed (m/min)	Machine-room Clear Height (mm)	Hook Capacity (Tons)
1800/2000	60/90/105/120/150	2500	4

Hoistway and Machine Room

Load (kg)	Speed (m/min)	Car Size (mm)		Door Opening (mm)		Front Wall Arrangement (mm)		Hoistway Dimension (mm)	Machine Room Size (mm)	Reaction Loading (KN)							
		Internal (a×b)	External (A×B)	Type	Width	L1	L2			X×Y	S×T	Machine Room			Pit		
												R1	R2	R3	R4	R6	R7
1800	60	2200×1700	2250×1885	2P-CO	1200	650	650	2700×2400	2950×2400	175	125	245	205	85	20		
	90									185	125	260	220	100	25		
	105									190	130	270	230	110	30		
	120									190	130	270	230	110	30		
2000	60	2200×1850	2250×2035	2P-CO	1200	650	650	2700×2550	2950×2550	185	125	260	215	90	20		
	90									190	130	270	225	100	25		
	105									195	135	280	235	115	30		
	120									195	135	280	235	115	30		

- Note:
- 1) The above information and dimensions are based on GB standards.
 - 2) Configuration is without counterweight safety gear.

Hoistway and Machine Room






- Note:
- ① Items with "*" shall be furnished by building contractors.
 - ② Hoistway shall not be located next to bedrooms, classroom, ward, library or any other places where low noise is required.
 - ③ The hoistway construction shall be reinforced concrete ring beam with strength C25 or whole hoistway of reinforced concrete wall. If you have other situations, please contact us.
 - ④ For hoistway and machine room details, please contact us.
 - ⑤ Unit of dimension shall be in mm unless otherwise stated.

Load (kg)	Speed (m/min)	Machine-room Clear Height (mm)	Hook Capacity (Tons)
1800/2000	60/90/105/120/150	2500	4

Hoistway and Machine Room

Load (kg)	Speed (m/min)	Car Size (mm)		Door Opening (mm)		Front Wall Arrangement (mm)		Hoistway Dimension (mm) X×Y	Machine Room Size (mm) S×T	Reaction Loading (KN)						
		Internal (a×b)	External (A×B)	Type	Width	L1	L2			Machine Room			Pit			
										R1	R2	R3	R4	R6	R7	
1800	60	2200×1700	2250×1885	2P-CO	1200	1075	675	3150×2150	3150×2450	175	125	245	205	85	20	
	90									185	125	260	220	100	25	
	105									190	130	270	230	110	30	
	120															
	150															
2000	60	2200×1850	2250×2035	2P-CO	1200	1075	675	3150×2300	3150×2550	185	125	260	215	90	20	
	90									190	130	270	225	100	25	
	105									195	135	280	235	115	30	
	120															
	150															

- Note:
- 1) The above information and dimensions are based on GB standards.
 - 2) The above information and dimensions are based on left side counterweight.
 - 3) Configuration is without counterweight safety gear.



- Note:
- ① Items with "*" shall be furnished by building contractors.
 - ② Hoistway shall not be located next to bedrooms, classroom, ward, library or any other places where low noise is required.
 - ③ The hoistway construction shall be reinforced concrete ring beam with strength C25 or whole hoistway of reinforced concrete wall. If you have other situations, please contact us.
 - ④ For hoistway and machine room details, please contact us.
 - ⑤ Unit of dimension shall be in mm unless otherwise stated.


Load (kg)	Speed (m/min)	Machine-room Clear Height (mm)	Hook Capacity (Tons)
1050	60/90/105	2100	3
	120/150/180	2450	4

Deep Car

Load (kg)	Speed (m/min)	Car Size (mm)		Door Opening (mm)		Front Wall Arrangement (mm)		Hoistway Dimension (mm)	Machine Room Size (mm)	Reaction Loading (KN)						
		Internal (a×b)	External (A×B)	Type	Width	L1	L2			X×Y	S×T	Machine Room			Pit	
1050	60	1100×2100	1150×2285	2P-CO	900	430	430	1960×2500	1960×2500	R1	R2	R5	R3	R4	R6	R7
	67.6									40.2	5.5	135	113	42	3	
	90					70.4	42.1	5.5	145	123	50	5				
	105					77	48	6	165	145	60	7				
	120					78	55	7	195	165	65	7				
1050	150	1300×1900	1350×2085	2P-CO	900	470	430	2000×2500	2000×2500	129	86	—	220	190	78	13
	180									67.6	40.2	5.5	135	113	42	3
	60					70.4	42.1	5.5	145	123	50	5				
	90					77	48	6	165	145	60	7				
	105					78	55	7	195	165	65	7				
1050	120	1300×1900	1350×2085	2P-CO	900	570	430	2100×2300	2100×2300	129	86	—	220	190	78	13
	150									77	48	6	165	145	60	7
	180					78	55	7	195	165	65	7				





- Note:
- 1) The above information and dimensions are based on GB standards.
 - 2) The above information and dimensions are based on left side counterweight.
 - 3) Configuration is without counterweight safety gear.

Maximum Allowable Stretcher Size (Deep Car) :



Car Internal Size (a×b) (mm)	Maximum Stretcher Length (L)	Lift Landing Depth (mm)
1100×2100	2100	≥2100
1300×1900	1900	≥1900

Hoistway and Machine Room



- Note:
- ① Items with "*" shall be furnished by building contractors.
 - ② Hoistway shall not be located next to bedrooms, classroom, ward, library or any other places where low noise is required.
 - ③ The hoistway construction shall be reinforced concrete ring beam with strength C25 or whole hoistway of reinforced concrete wall. If you have other situations, please contact us.
 - ④ For hoistway and machine room details, please contact us.
 - ⑤ Unit of dimension shall be in mm unless otherwise stated.

Load (kg)	Speed (m/min)	Machine-room Clear Height (mm)	Hook Capacity (Tons)
1050	60/90/105	2100	3
	120/150/180	2450	4


Hoistway and Machine Room

Wide Car

Load (kg)	Speed (m/min)	Car Size (mm)		Door Opening (mm)		Front Wall Arrangement (mm)		Hoistway Dimension (mm)	Machine Room Size (mm)	Reaction Loading (kN)								
		Internal (a×b)	External (A×B)	Type	Width	L1	L2			X×Y	S×T	Machine Room		Pit				
												R1	R2	R3	R4	R6	R7	
1050	60	2000×1200	2050×1423	2S-2P	1200	980	120	2500×1850	2500×1850	66	40	135	113	42	3			
	90									69.5	42	145	123	50	5			
	105									76	50	165	150	60	7			
	120									89	60	180	175	66	7			
	150									125	93	229	195	80	13			
1050	60	2000×1200	2050×1385	2P-CO (Door offset)	1000	800	500	2500×1800	2500×1800	66	40	135	113	42	3			
	90									69.5	42	145	123	50	5			
	105									76	50	165	150	60	7			
	120									89	60	180	175	66	7			
	150									125	93	229	195	80	13			


- Note:
- 1) The above information and dimensions are based on GB standards.
 - 2) Configuration is without counterweight safety gear.

Maximum Allowable Stretcher Size (Wide Car):




Car Internal Size (a×b) (mm)	Opening Width (mm)	Maximum Stretcher Size (L×W) (mm)	Lift Landing Depth (mm)
2000×1200	1200	1900×550 Stretcher A	≥1500
2000×1200	1000	1900×550 Stretcher B	≥1500

Elevation of Entrance



Structure Opening of Entrance




Type	AS-1X	SS-1X
W	10	25
D	10	25

- Note:
- Structural opening of entrance shall be furnished by building contractor.
 - Unit of dimension shall be in mm unless otherwise stated.
 - Applicable only when fireman operation function with fireman switch is located at lift landing.


The followings shall be furnished by building contractors:

- Building Structure
- Wall and Floor Finishes
- Grouting Work

Narrow Jamb (AS-1X)




Wide Jamb (SS-1X)



The followings shall be furnished by building contractors:

----- Electrical Equipment

— Cable



Note:
 ① Main Power Supply: Three-phase, five wires system, AC380V 50Hz.
 ② Lighting Power Supply: Single-phase, three wires system, AC220V 50Hz.

Item	Works to be provided by building contractor
Main Power Supply	To provide power supply switch around the entrance of machine room. To install facilities to ensure that power supply voltage fluctuation shall be within $\pm 7\%$.
Lighting Power Supply	To provide lighting power supply for car lighting, fan and indicator.
Ventilation Device	To provide mechanical ventilation to the machine room to ensure that the temperature in the machine room is maintained at below 40°C.
Pit light, Switch Socket Outlet	To provide single phase AC 220V, 10A switch socket outlet and pit lighting with switch below the entrance floor level for maintenance purposes.

Working environment of the elevator shall be as follow

1. Ambient temperature shall be between 5°C to 40°C.
2. Maximum relative humidity is 90%, and the monthly mean minimum temperature should be below 25°C.
3. Supply voltage fluctuation shall be within $\pm 7\%$.
4. Surrounding environment shall be free from explosive & corrosive hazard, anti-insulation and conductive particles atmosphere.

About hoistway and machine-room

1. Hoistway walls (including reinforced concrete ring beams) should be vertical, and the allowable deviation for the hoistway verticality is:
 Total Height \leq 30m:0~+25mm.
 30m<Total Height \leq 60m:0~+35mm
 Total Height>60m:0~+50mm
2. Hoistway walls shall be 200mm concrete walls.
3. Elevator hoistway is preferably not located in the space above accessible area. If the actual situation cannot meet the regulations, please contact us.
4. If elevator hoistway is of steel structure construction, please contact us.
5. Hoistway and machine room walls, floors and roofs should be able to absorb a large number of elevator operation noise.
6. Hoistway and machine room should not be located directly adjacent to bedrooms, classrooms, wards, library or any other places where low noise is required. Where such arrangements need to be imposed, the building contractors must be responsible for taking measures of sound insulation and cushioning.

Work to be done by Building Contractors

1. The preparatory work for elevator installation outlined below should be undertaken by building contractors in accordance with Hitachi drawing and applicable national or local codes and regulation.
2. Prepare hoistway with proper framing and enclosure, suitable pit of proper depth with drains and water-proofing if required, properly lighted and ventilated machine room of adequate size with concrete floor, access door, ladder and guards as required.
3. Provide and/or cut all necessary holes, chases, and openings and finish after equipment installation.
4. Supply and secure all supports, reinforced concrete slabs, etc., necessary for installation of the machinery, doors, buffers, etc.
5. Furnish all necessary cement and/or concrete for grouting-in of brackets, bolts, machine beams etc.
6. Prepare and erect suitable scaffolding and protective measures for the works in progress.
7. Furnish main for three-phase electric power and single-phase lighting supply to hoistway, following the instructions of the elevator contractors on outlet position and wire size.
8. Provide, free of charge, a suitable theft-proof storage area for materials and tools during erection work.
9. Supply electric power for lighting of work area, installation work, elevator testing and spray painting.
10. Suspension hook in the machine room with required loading as shown in this catalogue.

Note

Note
